No.	Item of works	Unit	Rate	Quantity	Rate to be quoted in	
					Figures	Words
	II. Cast Iron Pipe Sluice at R. L. 45.00.		Rs. a. p.		Rs.	Rs.
1	Earthwork excavating foundation cut opening the bund and refilling with watering and consolidation	C.yd.	0 5 0	118		
2	Stone jelly concrete in cement mortar 1 : 5 : 10	C.ft.	0 5 0	206		
3	Burnt stone slabs 6″ thick dressed and fixed in cement mortar	S.ft.	0 6 0	48		
4	Burnt size stone in cement mortar 1 : 6 ..	C.ft.	0 5 6	298		
5	Cutting holes in the slabs	Each	0 8 0	5		
6	Pointing with cement mortar 1 : 3	Sqr.	3 8 0	3.08		
7	Plastering with cement mortar 1 : 3.. ..	,,	8 0 0	0.32		
8	Providing and fixing jelly wood plug and iron rod with locking arrangement, etc., complete	Each	12 0 0	1		
9	Providing, carting and fixing cast iron pipe 6″ dia. including jointing, etc., complete ..	R.ft.	2 10 0	30		
	III. Masonry Waste Weir R. L. 51.00 (130 feet long).					
1	Earthwork excavation for foundation for the bodywall	C.yd.	0 3 0	547		
2	Stone jelly concrete in cement mortar 1 : 5 : 10	C.ft.	0 5 0	1,380		
3	Size stone in cement mortar 1 : 6 including cement pointing	C.ft.	0 5 6	2,624		
4	Providing cement concrete 1 : 2½ : 5 for coping slab including cement plastering 1 : 3, etc., complete	C.ft.	0 10 0	56		
5	Providing new rough stone revetment with jelly backing and jelly wedging with required lead and lift	C.yd.	1 4 0	320		
6	Rough stone revetment old with new jelly backing and jelly wedging including required lead and lift.	C.yd.	0 10 0	166		

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Notification dated 5th March 1940.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 26th March 1940, for the work of construction of masonry anes across Enne Hole and installing automatic syphons at Mudigere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1940.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 225 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for the work of construction of masonry anes across Enne Hole and installing automatic syphons at Mudigere Taluk," in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Sanitary Engineer will be final and legally binding.

Estimate of the approximate quantities for construction of masonry Anes across Enne Hole and installing automatic syphons at Mudigere Taluk.

No.	Items of work	Unit	Quantity
1	Removing loose boulders lying at site and arranging the same in front of Ane for protection	C.yd.	20×2=40
2.	Removing sandy and slushy soil, etc., and exposing bed for laying foundation	,,	50×2=100
3	Removing hard rock by blasting and stocking the same	,,	20×2=40
4	Chiseling and removing rock for preparing bed for foundation	S.ft.	300×2=600
5	Cement concrete in the proportion of 1 : $2\frac{1}{2}$: 5 for foundation	C.ft.	700×2=1,400
6	Constructing body wall with size stone in cement mortar (1 : 4)	,,	636×2=1,272
7	Constructing an R.C.C. retaining wall in front of apron with masonry reinforcement	,,	20×2=40
8	Providing and fixing De'Villier's syphons with $1\frac{1}{2}$" diar. pipe, drum, connections, fixing, etc., complete as per design	Each	2×2=4
9	Cement pointing to ane stone masonry	Sqr.	6.00×2=12.00
10	Constructing rough stone revetment including jelly filling complete	C.yd.	75×2=150
11	Plastering with cement mortar (1 : 2)	Sqr.	1.00×2=2.00
12	Laying cement concrete slab over the body wall on Ane including cement plastering (1 : 2)	C.ft.	62×2=124

K. S. HUTCHA RAO,
Sanitary Engineer.

MISCELLANEOUS DEPARTMENTS.

GOVERNMENT OF MYSORE—ELECTRICAL DEPARTMENT.

OFFICE OF THE CHIEF ELECTRICAL ENGINEER IN MYSORE, BANGALORE.

Abstract Notification dated 26th February 1940.

Attention is drawn to this office Notification, dated 26th February 1940, inviting tenders for No. 10 B.W.G. Galvanized Wire, published in Part VI, pages 444-445 of the *Mysore Gazette*, dated 29th February 1940. The last date of receiving tenders is 16th March 1940, 12 NOON.

M. HAYATH,
For *Chief Electrical Engineer.*